

The Fujitsu logo, featuring the word "FUJITSU" in a serif font with an infinity symbol above the letter "J".

FUJITSU

The words "CASE STUDY" in a white, serif font, centered within a large, red, vertically-ribbed oval shape that resembles a lens or a window.

CASE STUDY

The Airstage logo, featuring the word "AIRSTAGE" in a bold, italicized, sans-serif font with a stylized swoosh above the letter "A".

AIRSTAGE™

Ft. Huachuca Greeley Hall
Ft. Huachuca, Arizona

Ft. Huachuca Greeley Hall

Project Name

Ft. Huachuca Greeley Hall

Location

Ft. Huachuca, Arizona

Completion Date

March 2015

The Team

Owner

United States Army

Engineer

US Army Corp of
Engineers

HVAC Contractor

Temco Air Environmental

HVAC Distributor

Air Cold

HVAC Representative

LDP Associates

The Army was happy with the capabilities of their system at the Arms Simulation Building and was satisfied with the installation, so they decided to install a system in one of their conference centers in Greeley Hall.

Design Challenge

Since the fire alarm would need to be disabled and thus shutting down the entire building, the system had to be installed without the use of flame brazing. The contractor made all brazed connection at his shop and brought rolled soft copper to the job site. The copper was then unwound and fed through chases to the roof to the outdoor unit. The fact that the contractor could mix and match hard and soft copper made the installation go very smoothly. As well, the contractor was happy that all other connections were flared, making it easy to prepare the copper in the field without having to use flame.

Why Fujitsu Was Chosen

Fujitsu was chosen for its successful installation on a previous job at the Arms Simulation building. The fact that the job went very smoothly and that they system was operating quietly and efficiently allowed for the end user to make an easy choice for their heating and


cooling needs. As well, the indoor units being in a conference room, needed to be as quiet as possible.

The Results

The Army was very happy with the installation. They found the room to be quieter than expected, even when running at full fan speed, and with the installation at the previous site, they knew they were getting a reliable, energy efficient system.

Customer Testimonial

The contractor was able to use the access elevator to get the unit onto the roof. Being creative, they made a base with wheels on it. They were able to pre-mount the outdoor unit on the base/cart and bring it to the jobsite. They then rolled the unit from the ground, up on the service elevator, and onto the roof into the location they needed. All of the site portion of this exercise was completed by one man. Pretty impressive and creative!




AIRSTAGE VRF EQUIPMENT INSTALLED

- (1) AOUA72TLBV VR-II Series Outdoor Units
- (1) ARUM30TLAV VR-II Medium Static Pressure Duct
- (1) ARUH48TLAV VR-II High Static Pressure Duct
- (1) UTY-DCGY Central Remote Controller
- (1) UTY-VLGX Network Converter for LONWORKS
- (2) UTY-RNRU Individual Touch Panel Controller (Wired Remote)
- (1) UTY-XWZXZB External Input Wired V-II for Control Input Port
- (1) UTP-BX090A Indoor Separation Tube
- (2) UTP-RU01BH Single Type Refrigerant Branch Unit



Individual Touch Panel Controller



VR-II Series Outdoor units



- ISO9001
- ISO14001

Fujitsu General America, Inc.

353 Route 46 West
 Fairfield, NJ 07004
 Toll Free: (888) 888-3424
 Local: (973) 575-0380

www.airstagevrf.com
www.fujitsugeneral.com
 A subsidiary of
 Fujitsu General Limited